

DIRECTORATE FOR
GEOSCIENCES

OFFICE OF POLAR PROGRAMS

Designing Cyberinfrastructure for the Antarctic Research Vessel (ARV)

CI4MF 2024 18 January 2024

NSF ARV Team

Stephanie Short, ARV Program Lead

Tim McGovern, ARV Program Manager

Caitlin Jarecki, ARV Assistant Program Manager (USN PEO Ships)

Mike Prince, ARV Project Manager

Tim Howard, OPP/AIL Information Technology Support Manager


Preliminary Design Rendering



OFFICE OF
POLAR PROGRAMS



Overview – Replacement for NBP



	<i>Nathaniel B. Palmer</i>	Antarctic Research Vessel	
Length	309 ft	365 ft	Bigger
Sci/Tech Berthing	45	55*	More scientists
Total Lab Space	3,805 sq ft	4,497 sq ft	More lab space
Working Deck Space	4,054 sq ft	7,197 sq ft	More deck space
Endurance	65 days	90 days*	Longer endurance

**AND greater icebreaking capability
≥4.5 ft @ 3 kts (Polar Class 3)***

**Key Performance Parameter (KPP)
Current Design & Hull Form meets all KPPs*

ARV Placemat with Specifications



OFFICE OF
POLAR PROGRAMS

Antarctic Research Vessel (ARV) Preliminary Design Placemat



REFERENCE MISSION

Duration	90 days
----------	---------

DIMENSIONS

Length, Overall	365.0 ft
Length, BP	349.0 ft
Beam, Overall	80.0 ft
Beam, WL	79.3 ft
Design Draft	32.5 ft
Working Deck Freeboard	13.0 ft
Displacement (Design Draft)	13,430 LT
Light Ship Weight (including margins)	9,790 LT
Deadweight	3,640 LT

ACCOMMODATIONS


Ship's Crew	29
Science Complement	55 (including 2 ADA-accessible berths)

PROVISIONS

Freeze	90 days
Chill	90 days
Dry	90 days

AVIATION

UAV Launch/Recovery	150 lbs
UAV Hangar	1,472 ft ²
Helicopter Landing	Bell 407 Airbus H125



MACHINERY SYSTEMS

Azimuthing Podded Propulsors	2 x 9.5 MW
Bow Thrusters	1 x 1.9 MW
Ship Power Plant	22.3 eMW
Propeller	2 x 16.0 ft FPP

AUXILIARY SYSTEMS

A/C Plants	Qty 3 @ 205t
Fire Suppression	NOVEC and Water Mist
Mission Fuel Capacity	60,000 gal
Ship Service Battery	2.7 MWh
Wastewater Holding	20 days

COMMUNICATIONS

HF Transmit and Receive
Ku, Ka, C, and UHF SATCOM
GMDSS
INMARSAT
UHF/VHF LOS Comms
UAS Comms
Fleet Broadband

NAVIGATION

AIS
ECDIS
S & X Band Radar
Ice Radar
DGPS

MISSION EQUIPMENT

2 Main Deck Cranes	Maximum reach: 65ft 70,000 lbs @ 50ft
Portable Utility Crane	4,000 lbs @ 40ft
Forward Crane	4,000 lbs @ 40ft
Stern A-Frame	80,000 lbs slewing
Side A-Frame	
Meteorology Mast	1
Atmospheric Mast	1
CTD Hydroboom	Fast-acting, Reaches water level
Piston Core LARS	40m
Multibeam Sonar Suite	
Sonar Drop Keel	0 ft / 3 ft / 10 ft
Container Quantity	20 TEU

PERFORMANCE

Open Water	
Maximum	> 17 kt
Cruise	11 kt
Quiet	8 kt
Ice	
Continuous 3 kt	> 4.5 ft + 1 ft snow
Continuous 6 kt	> 1.6 ft
Turning out	> 4.5 ft
Range	> 17,000 nm
Towing	
4 kt	25,000 lbs
6 kt	10,000 lbs

CLASSIFICATION

ABS #A1 Oceanographic	#AMS
CCO-POLAR (-35°C, -45°C)	Ice Class PC3
#ACCU	CRC
Unrestricted service	R2
EEDI-PH3	ENVIRO
HAB+ (WB)	BWT+
ESS-LIBATTERY	HYBRID IEPS
ILM	UWILD
POT	

MISSION SPACES

Containers	8 in Science Hold 12 on Weather Decks
Lab Area, Total	8,263 ft ²
Aft Work Deck	7,724 ft ²
Science Stores	42,571 ft ³
Side Deck Length	170 ft
Baltic Room Area	704 ft ²
HAZMAT Storage	214 ft ²
Science Observation Deck	1,163 ft ²




November 7, 2023


General Arrangement – Profile



Drawings & Reports go to:
<https://future.usap.gov/arv-doc-library/>



ARV Schedule




Next Steps:

- RFP and Selection of the Vessel Integrator to complete the project. (CY 24)
- Final Design Phase (CY 24-26)
- Final Design Review (CY 26)
- Appropriation and Approvals to start Construction Stage (CY 26)

- NSF Research Infrastructure Guide - <https://www.nsf.gov/pubs/2021/nsf21107/nsf21107.pdf>
 - Section 6.3 – Cyber Security Requirements
- ARV Performance Specification & Science Mission Requirements
- ARV Project Execution Plan
 - Section 7 and Appendix 13 – Systems Engineering Plan includes Cyber IPT
 - Section 12 – Cyber Infrastructure and Cyber Security

Table 1. IPT & WG Functions


IPT/ WG Name	Responsibility	Members	Meeting Frequency
Systems Engineering IPT [SE IPT]	Coordinates SE activities: Requirements decomposition, allocation, traceability and compliance; technical budgets; KPPs, trade studies, interface management.	Led by SE. SME's from each IPT as required NSF Representative	Monthly Final Design through Construction Stage.
Cybersecurity IPT [CYBER IPT]	Coordination and review of the activities related to the development and implementation of Hardware (HW) and Software (SW) and network enclaves to satisfy Cybersecurity requirements.	Led by Cyber Lead, SMEs invited as required. NSF Representatives	Monthly Final Design through Construction Stage.




ARV Project Team – Cyber = Key Component



ARV Technical Project Team





CI – Topside Arrangement – Comms & Sensors



CI – Acoustic Systems




ITEM NO.	QTY PROVIDED	DESCRIPTION
1	1	TRANSDUCER: DEEP WATER, MULTI-BEAM, 1'
2	1	TRANSDUCER: DEEP WATER, MULTI-BEAM, 1'
3	1	TRANSDUCER: SHALLOW WATER, MULTI-BEAM, 1', TX
4	1	TRANSDUCER: SHALLOW WATER, MULTI-BEAM, 1', RX
5	1	ACOUSTIC DOPPLER CURRENT PROFILER 38 KHZ
6	1	ACOUSTIC DOPPLER CURRENT PROFILER 70 KHZ
7	1	ACOUSTIC DOPPLER CURRENT PROFILER 300 KHZ
8	1	SUB-BOTTOM PROFILER, 3'
9	1	ACOUSTIC RELEASE TRANSDUCER 12 KHZ
10	1	USBL
11	2	SPEED LOG
12	2	19" CENTERBOARD SPARE
13	5	HYDROPHONE
14	1	FORWARD LOOKING CAMERA
15	1	FORWARD LOOKING SONAR
16	1	WBESS TRANSDUCER 18 KHZ
17	1	WBESS TRANSDUCER 38 KHZ
18	1	WBESS TRANSDUCER 70 KHZ
19	1	WBESS TRANSDUCER 120 KHZ
20	1	WBESS TRANSDUCER 200 KHZ
21	1	WBESS TRANSDUCER 333 KHZ



DETAIL 5-2B
CENTERBOARD ARRANGEMENT


CI – Lab Spaces – Server Room




CI – Network Diagrams – Three Networks




Vessel Network Boundary (Cont.)



CI – Network Diagrams – Vessel Network



Guest Network Boundary




The end result – fitting it all in...



Lessons Learned from other projects:

- Model the routing of cables and placement of equipment before starting installation.
 - 3D modeling down to very small (less than 1" diameter) cables
 - 3D modeling of all equipment foundations and locations
- Make sure all related equipment is identified and located in detailed construction drawings.
 - Finding a suitable location after construction has started is problematic and uses space allocated for some other use.
- Specify actual equipment (make/model) as late as possible in the construction process.
 - Design and model representative space, weight, power, cooling, connections and locations that will accommodate the eventual equipment selection. "SWaP-C" mentioned earlier.
 - Don't underestimate size, weight, power requirements in early design efforts
- Visualize and diagram all connections, integration and utilization of all Cyberinfrastructure as part of creating the design documentation.

- ARF (UNOLS) Cyber Working Group (CIWG)
 - Weekly Meetings
- ARV (UNOLS) Facilities Groups
 - Multibeam Advisory Committee (MAC)
 - UHDAS – ADCP Data Acquisition
 - Shipboard Automated Meteorological and Oceanographic System (SAMOS)
 - Rolling Deck to Repository (R2R)
- Trusted CI – Cyber Security Support
- Compass CI – Cyber Infrastructure Support



Science Advisory Subcommittee (SASC)

Reports:

<https://future.usap.gov/arv-community-input/>

- Dr. Amy Leventer, (Chair) Colgate University
- Ms. Alice Doyle, UNOLS
- Dr. Carlos Moffatt, Univ of Delaware
- Dr. Deborah Steinberg, VIMS
- Dr. Kristin O'Brien, UAF; GEO AC Rep

Past Members

- Dr. Patricia Quinn, NOAA/PMEL
- Dr. Clare Reimers, OSU
- Dr. Bruce Appelgate, UCSD/Scripps

*** Seeking nominations for 3 new members**



CI Recommendations for the Antarctic Research Vessel (ARV)

Author(s): Anirban Mandal, Ilya Baldin, Erik Scott, Ewa Deelman (CI Compass)

Date: September 15, 2023

1. Develop canonical science use cases to help exercise the CI system.
Develop a small set of validating science use cases, both current and projected, representative of the scientific experiments performed by the broader NSF Office of Polar Programs (OPP) researcher community.
 - a. Attach soft performance expectations and any other specific requirements (compute, network, storage) for each of the validating canonical science use cases.
2. Design “CI Cruise” to overlap with ship design reference mission to validate canonical science use cases.
Develop a detailed plan for piggybacking design and evaluation of the shipboard CI capabilities with respect to the validating science use cases during the 90-day ship design reference missions. This can be referred to as “CI Cruise”.
3. Develop and test on a small-scale twin of shipboard CI infrastructure.
Develop a sandbox testing platform that is a small-scale twin of the planned CI for the research vessel on shore-side, and identify a small number of teams willing to test drive the science use cases in that small-scale twin
4. Develop vessel IT operational use cases.
Develop canonical operational use cases to design, test and validate the general IT operations that are required during all cruises. These use cases should exercise all IT functions in the ship, e.g. external comms, internal comms, PA, entertainment systems, ship alarms, CCTV, email, guest WiFi network, DNS and other network functions, etc.

Design Reference Mission (DRM) – CI Version



Table 3: DRMC1 Thwaites/Pine Island Bay – Vessel Movement Daily Activities

Activity Start		Activity End		Activity Hours	Location	Operation	Cruise days	Activity Type
Date	Shift	Date	Shift					
14-Dec	AM	14-Dec	AM	12	Punta Arenas, Chile (PUQ)	Depart	1	Hotel only
14-Dec	PM	20-Dec	PM	156	PUQ to Amundsen Embayment	Transit open ocean (Approx 1,590 nm)	1 - 7	Open water transit
21-Dec	AM	22-Dec	PM	48	Amundsen Embayment	CTD work	8 - 9	On station
23-Dec	AM	24-Dec	AM	36		Trace metal tow-fish	9 - 11	Acoustically quiet transit
24-Dec	PM	24-Dec	PM	12		Sea glider deployment	11	On station
25-Dec	AM	26-Dec	PM	48		Transit - first and second year ice	11 - 13	Icebreaking
27-Dec	AM	27-Dec	PM	24		Transit - first and second year ice	13 - 14	Icebreaking
28-Dec	AM	30-Dec	AM	60		CTD work	15 - 17	On station
30-Dec	PM	30-Dec	PM	12		Sea glider deployments	17	On station
31-Dec	AM	31-Dec	AM	12		Transit - first and second year ice	18	Icebreaking
31-Dec	PM	31-Dec	PM	12		Mega-core/CTD	18	On station, DP
1-Jan	AM	1-Jan	AM	12		VMP transect	19	Acoustically quiet transit
1-Jan	PM	1-Jan	PM	12		Transit light ice	19	Ice transit

Figure 1: Future Thwaites Glacier Cruise Track




Table 2: DRMC1 Thwaites/Pine Island Bay – Vessel Movement Summary

Location	Fair Weather Duration (days)		
	Southern Ocean	Amundsen Embayment	Amundsen Sea
Open water transit	10	-	-
Acoustically quiet transit	-	16	-
Icebreaking	-	9	-
On station	-	37.5	-
On station, DP	-	10	-
Deployment	-	3	-
Hotel only	1	-	0.5
Ice Transit	-	2	1
Totals (90-day total mission duration)	11	77.5	1.5

Compass CI Recommendation # 2 is to create a companion CI Cruise Scenario to evaluate the CI/CS requirements to support this Design Reference Mission.

- Final Design Phase
 - Continue to develop the Ship-wide Network Diagram moving from a Logical Diagram to a Physical Diagram
 - Depicting cable type
 - Determining exact placement of individual equipment
 - Developing rack diagram
 - Continue Development of Cyber Security Controls
 - Security Control Traceability Matrix (SCTM) – 5E1-402-P001
 - NIST SP 800-53 Rev 5
 - 356 controls shaping three networks' security stance
 - Sets subsequent phases up for cyber success
 - Continue reaching out to the Science and Cyber Community
 - Attendance at UNOLS CIWG Ship Ops and Tech Services meetings provide beneficial insight
 - Compass CI to review updated Network Diagrams and CI details
 - Trusted CI to review Cyber Security planning
 - NSF CI/CS program officers and USAP CI/CS expertise continued involvement in ARV project development.
- Construction Stage
 - Continue Design Development w/Ship Builder – Source specific vendors and equipment
 - Installation of CI and Testing



New Antarctic

Planning for the Next Generation of Oceanographic Research Vessel

Ship Design

Current Science Missions

Key performance parameters, operational requirements, and other information found here.

Science Mission Requirements (PDF)

Placemat

The ARV Preliminary Design Placemat is a key performance parameter document for the ARV. It lists overall hull dimensions, installed equipment, and other information.

DIMENSIONS	
Length Overall	345 ft
Length BP	325.5 ft
Beam Overall	73.5 ft
Beam LWL	72 ft
Draft FLD Load Line	28 ft
Draft Full Load	28 ft
Draft Lightship	17 ft

PERFORMANCE	
Open Water	11 kt T / 12 kt O
Cruise	11 kt T / 12 kt O
Quiet	8.5 kt
Ice	
Continuous 3 kt	4.5 ft
Continuous 6 kt	1.6 ft
Turning out	4.5 ft
Range	17,000 nm

ACCOMMODATIONS	
Ships Crew	29
Deck	15
Engineering	9
Stowage	5
NSF Science Party	2
ADA Accessible	2
Scientists	30
Waterwater (days)	207 / 400

PROVISIONS	
Freeze	90 days
Chill	45 days
Dry	90 days

AVIATION	
UAV Launch/Recovery	150 lbs
UAV Hangar	No IP-5
UAV Workshop	

COMMUNICATIONS & COORDINATION	
HF Terminal	
C-Band SAT	
UHF SATCOM	
GMDSS	
INMARSAT F	

Design placemat of the new Antarctic Research Vessel

Credit: NSF, Leidos Inc.

New Antarctic Research Vessel (ARV)

Planning for the Next Generation of Oceanographic Research Vessel

Documents Library

Concept Design

- Conceptual Design Memo
 - Leidos ARV Conceptual Design Memo
- Concept Design Reports (Glosten Documents)
 - 19136 Concept Design Report
 - 19136 Science Berthing Study Project Memorandum
 - 19136.01 ARV Deck De-icing Systems Study - Status Update 09/29/20
 - 19136.01 ARV Ice Environment Study - Status Update 09/25/20
 - 19136.01 ARV Jumbo Piston Coring Study - Status Update 09/25/20
 - 19136.01 - Manning Study
- Trade Off Studies
 - 19136-000-01 ARV USCG Compliance Study Report
 - 19136-000-02 ARV Propulsor Study Report
 - 19136-000-03 ARV Power Systems Study Report
 - 19136-000-04 ARV Climate Study Report
 - 19136-000-05 ARV Seakeeping Study Report
 - 19136-000-06 ARV Ice Environment Study Report
 - 19136-000-07 ARV Green Ship Alternatives Report
 - 19136-000-08 ARV Autonomous Vehicle Handling Study Report
 - 19136-000-09 ARV Deck De-icing Study Report
 - 19136-000-13 ARV Triple Propulsor Report
- Applicable UNOLS Guidelines and Reports
 - American Disabilities Act (ADA) Guidelines for UNOLS Vessels

FOR OFFICIAL USE ONLY

May 18, 2022



What is Future USAP?



Future USAP is a part of the United States Antarctic Program (USAP). Funded by the National Science Foundation, Future USAP is dedicated to long range investments in Antarctic infrastructure.

News and Updates



Wednesday - July 06, 2022
Construction of New Pier at Palmer Station Now Complete

future.usap.gov/arv

Antarctic Research Vessel Summary



OFFICE OF
POLAR PROGRAMS

- ❖ ~20 years of sustained scientific demand
- ❖ Continued ability to support cutting edge NSF research for the next 40 years
- ❖ Enhanced capabilities over existing USAP research vessel
- ❖ Strong Teaming with Industry



Preliminary Design Rendering



OFFICE OF
POLAR PROGRAMS



Questions

